

NOTE:
WHITEBLOCK 3" WALLED H20 LOADED VAULT
INSIDE DIMENSIONS: (White Block Large Meter Yault.)

DRAWING NOT TO SCALE

11'6" L x 7'6" W 5'10" tall I.D. (VAULT AND HATCH MUST BE TRAFIC RATED...)

NOTES:

1. ALL PIPING AND EQUIPMENT SUPPLIED BY NORTHWEST HYDRO TECH.
2. VAULT SUPPLIER WILL SUPPLY AN INDIVIDUAL WITH AT LEAST 10 YRS EXP. WITH CONTROL VALVE EQUIPMENT START—UP AND TROUBLE SHOOTING.
3. VAULT SUPPLIER TO PROVIDE 3 COPIES OF O&M MANUALS.
4. VAULT SHOWN INCLUDES ALL EQUIPMENT REQUIRED FOR A FULLY FUNCTIONING PRY STATION. THIS INCLUDES DELIVERY TO SITE.
5. VAULT SUPPLIER WILL OFF LOAD VAULT AND COORDINATE WITH INSTALLER DELIVERY. INSTALLER MUST PROVIDE ALL EXCAVATION AND FINAL CONNECTIONS.
6. DISINFECTION, FINAL GRADE AND ANY CONNECTIONS OUTSIDE OF THE VAULT ARE THE INSTALLERS RESPONSIBILITY.

BILL OF MATERIALS		
ITEM	QTY	DESCRIPTION
1	1	8" CLA-VAL 92G-01YBCSKC PRESSURE
		REDUCING/SUSTAINING VALVE W/X101 D.I.
		BODY EPOXY COATED SST TRIM 150LB FLANGE.
2	1	3" CLA-VAL 92G-01YBCSKC PRESSURE
		REDUCING/SUSTAINING VALVE W/X101 D.I.
		EPOXY COATED SST TRIM 150 FLANGE.
3	2	8"R/S/GATE VALVE 150 FLXFLC-509 NSF-61
		ANSI/AWWA WITH HAND WHEELS.
4	2	3" R/S GATE VALVE 150 FLXFLC-509 NNSF-61
5	2	2-1/2" 0-200 PSI GAUGE LIQUID FILLED WITH
		1/4 SST. ISOLATION VALVE.
6	1	WHITE BLOCK LARGE METER VAULT H-20
<u> </u>		RATED. ROUND KNOCK FOR PIPE.
7	4	ADJUSTABLE STEEL PIPE SUPPORTS
8	2	8" LINK SEAL ASSEMBLY
9	1	32" GMI COMPOSITE RING AND COVER
10	1	6' POLY LADDER WITH PULL UP SAFETY POST
11	2	8" X 3" D.I.T.'S
12	1	3" GROVE COUPLING
13	1	8" X 5' D.I. SPOOL FL. X P.E.
14	1	8" CLA-VAL H STRAINER
15	1	3" CLA-VAL H STRAINER
16	1	1" AIR VACUUM BREAKER W/ SST ISOLATION
		VALVE

NORTHWEST HYDRO TECH
P.O. BOX 1404
RATHDRUM, ID 83858
208-691-7430
E-MAIL: NWHYDROTECH@OUTLOOK.COM
WEB: NWHYDROTECH.COM

DETAIL NO.:

BSWSD: 26-19 BIG SKY WSD 363 STANDARD DRAWING

SCALE:

TYPICAL 8" X 3" PRV STATION

DATE:
FEBRUARY 2010
LAST REVISION:
MARCH 2016
CROSS REFERENCE WITH:
N/A